

CHANGE ORDER

CONSTRUCTION MANAGER-ADVISER EDITION

Owner
 Construction Manager
 Architect
 Contractor
 Field
 Other

PROJECT: **Loeb Stadium**
 (Name and address) **Main Street and Wallace Street**
Lafayette, Indiana

CHANGE ORDER NO.: **BP-8-1**

INITIATION DATE: **June 4, 2019**

TO CONTRACTOR: **Huston Electric, Inc.**
 (Name and address) **P. O. Box 4297**
Lafayette, IN 47903-4297

PROJECT NOS.: **6617**

CONTRACT FOR: **BP #8 - Electrical**

CONTRACT DATE: **June 4, 2019**

The Contract is changed as follows:

BP #8 VE Item #1 - Allow use of aluminum EMT conduit for all exposed and concealed conduit locations where not subject to physical damage http://www.americanconduit.com/wp-content/uploads/2013/03/Aluminum-EMT.pdf	Deduct	-\$3,800.00
BP #8 VE Item #2 - In all concealed areas above the APC-1 and MP-2 metal ceilings (if alternate is not accepted), allow use of PVC coated MC cable https://www.southwire.com/search/?q=Armorlite	Deduct	-\$18,960.00
BP #8 VE Item #3 - Allow use of MC cable in all exposed (above 8') and concealed areas where allowed by National Electrical Code and not subject to physical damage	Deduct	-\$13,420.00
BP #8 VE Item #5 - Utilize aluminum feeders for all conductors #8 and larger sized per NEC	Deduct	-\$22,840.00
BP #8 VE Item #6 - Allow all low voltage conduits to be grouped into larger conduits as allowed by NEC	Deduct	-\$5,650.00
BP #8 VE Item #7 - Allow use of PVC schedule 40 conduit in lieu of IMC conduit at all under and in slab locations	Deduct	-\$9,380.00
BP #8 VE Item #8 - Allow open cable installation with j hangers and cable tray for all low voltage systems installed in concealed locations	Deduct	-\$12,500.00
	Total Deduct	-\$86,550.00

Not valid until signed by the Owner, Construction Manager, Architect and Contractor.

The original (Contract Sum) (Guaranteed Maximum Price) was.....	\$	2,097,366.00
Net change by previously authorized Change Orders.....	\$	0.00
The (Contract Sum) (Guaranteed Maximum Price) prior to this Change Order was.....	\$	2,097,366.00
The (Contract Sum) (Guaranteed Maximum Price) will be (increased) (decreased) (unchanged) by this Change Order.....	\$	-86,550.00
The new (Contract Sum) (Guaranteed Maximum Price) including this Change Order will be.....	\$	2,010,816.00
The Contract Time will be (increased) (decreased) (unchanged) by		(0) days
The dated of Substantial Completion as of the date of this Change Order therefore is		Unchanged

NOTE: This summary does not reflect changes in the Contract Sum, Contract Time or Guaranteed Maximum Price which have been authorized by Construction Change Directive.

Kettelhut Construction, Inc.
 CONSTRUCTION MANAGER

740 Sagamore Parkway S., Lafayette, IN 47905
 ADDRESS

 6/11/19
 BY DATE

Huston Electric, Inc.
 CONTRACTOR

PO Box 4297, Lafayette, IN 47903-4297
 ADDRESS

 6/11/19
 BY DATE

American Structurepoint, Inc.
 ARCHITECT

7260 Shadeland Station, Indianapolis, IN 46256
 ADDRESS

 06.11.19
 BY DATE

City of Lafayette, Indiana Board Public Works and Safety
 OWNER

20 North 6th Street, Lafayette, IN 47901
 ADDRESS

 6/12/19
 BY DATE



June 10, 2019
RE: Loeb Stadium

Page 1 of 1

Dear Alex,

Huston is pleased to offer the following VE options for the Loeb Stadium project:

1. Allow use of aluminum EMT conduit for all exposed and concealed conduit locations where not subject to physical damage. - \$ 3,800.00
2. In all concealed areas above the APC-1 and MP-2 metal ceilings (if alternate is not accepted), allow use of PVC coated MC cable. - \$ 18,960.00
3. Allow use of MC cable in all exposed (above 8') and concealed areas where allowed by National Electrical Code and not subject to physical damage. - \$ 13,420.00
4. Eliminate the fire alarm devices in the outfield area. - \$ 2,600.00 **NOT ACCEPTED**
5. Utilize aluminum feeders for all conductors #8 and larger sized per NEC. - \$ 22,840.00
6. Allow all low voltage conduits to be grouped into larger conduits as allowed by NEC. - \$ 5,650.00
7. Allow use of PVC schedule 40 conduit in lieu of IMC conduit at all under and in slab locations. - \$ 9,380.00
8. Allow open cable installation with j hangers and cable tray for all low voltage systems installed in concealed accessible locations. - \$ 12,500.00

Total savings - \$ 89,150.00

We look forward to working with you on this project.

Sincerely,

Brady McKinney

Approved by the Board of Public Works and Safety on the _____ day of
_____, 2019.

Gary Henriott, President

Cindy Murray, member

Norm Childress, member

Ronald Shriner, member

Amy Moulton, member

ATTEST:

Mindy Miller, Deputy Clerk

Date: _____